




Notes (all drawings).

1. All dimensions are proposed and in metres unless otherwise stated.
2. All setting out is to be agreed on site with the Engineer prior to commencement of works.
3. All precast concrete (PCC) kerbing and edging shall be in accordance with BS7263, Part F.
4. Any voids between new kerbs and existing carriageway shall be reinstated with 10mm AC 10 close surf.
5. Surfaces between bituminous materials shall be saw cut to provide a clean vertical joint.
6. Vertical faces of existing bituminous materials shall be primed with bitumen. Existing horizontal or inclined surfaces shall be tack coated in accordance with Appendix 7/4.
7. New footway surfaces shall be laid with 1:40 crossfall towards carriageway unless otherwise stated with no point having a crossfall greater than 1:12.
8. Existing surfaces overlaid shall be swept clean prior to overlay and sprayed with tack coat.
9. All existing covers in areas to construction to be raised to suit new levels.
10. All existing road markings that conflict with the proposed are to be removed.






General key

 Existing lamp column to remain.






Site Clearance Key

-  Remove existing PCC kerb including bedding and backing and dispose of at Contractor's licensed tip. [c13 metres]
-  Remove existing PCC edging including bedding and backing and dispose of at Contractor's licensed tip. [c8 metres]
-  Excavate existing verge to 170mm below finished levels. [c27 square metres]









Drainage Key

-  Existing PCC trapped gully (to remain).
-  Existing PCC trapped gully to be removed and infilled or capped. [2No]
-  New PCC trapped gully with class D400 grate as KCC/SD/500/009.
-  Connection of 150Ø pipe to existing PCC chamber with mass concrete surround.
-  AG Adjust gully grating and frame.


Kerbing / Footway Construction Key

-  Overlay footway or carriageway with AC6 dense surf 100/150 20mm thick over AC10 regulating layer. Perimeter of surface course to be keyed into existing surface course to give a minimum layer thickness of 20mm. All joints to be saw cut. [c328 square metres]
-  Full footway construction Type A to KCC/1100/011/G. (Existing grass verge / unacceptable material to be excavated to a depth of 170mm below finished levels). [c28 square metres]
-  Proposed 125 x 255mm half battered kerbing (Type HB2). Variation B upstand 125mm to KCC/1100/001/D. [c167 metres]
-  Proposed 50 x 150mm PCC edging to KCC/1100/001/D. [c107 metres]
-  Existing buff PCC tactile paving slabs to be lifted and reset to new levels where necessary. Installed to KCC/1100/015. Blisters to align with tactiles on opposite side of road. [c3 square metres]


Sign & Lines Key


-  Non-illuminated traffic sign (refer to Sign Schedule).
-  Illuminated traffic sign (refer to Sign Schedule).
-  Sign to be removed (refer to Sign Schedule).
-  Sign position and orientation.
-  Road marking TSRGD 2016 Diagram number.
-  Existing road marking to be removed by mechanical scabbling.
-  Proposed road marking in white thermoplastic screed with applied solid glass bead.
-  Existing road marking (for information only). Some existing markings have been omitted for clarity.

Location plan (1:2000).




© Crown Copyright and database right 2020. Ordnance Survey 100019238.



0	30/06/2020	First issue.	PB			Project	Highsted Road new footway, Sittingbourne.		Drawing status	FOR CONSTRUCTION	
Rev	Revision Date	Purpose of revision	Drawn	Check'd	App'd	Drawing title	Location plan and notes.		Scale	1:2000 at A3	Do not scale
 <p>Kent County Council Ashford Highway Depot Henwood Industrial Estate Ashford TN24 8AD Tel: 03000 418181</p>									Drawing number	1819-LTP-SW-545-0030	
									Rev	0	
<p>This drawing is not to be used in whole or part other than for the intended purpose and project as defined on this drawing. Refer to the contract for full terms and conditions.</p>											





© Crown Copyright and database right 2020.
Ordnance Survey 100019238.





0	30/06/2020	First issue.	PB			Project Highsted Road new footway, Sittingbourne.	Drawing status FOR CONSTRUCTION		
Rev	Revision Date	Purpose of revision	Drawn	Check'd	App'd		Scale	1:150 at A3	Do not scale
 <p>Kent County Council Ashford Highway Depot Henwood Industrial Estate Ashford TN24 8AD Tel: 03000 418181</p>						Drawing title Site clearance. and earthworks.	Drawing number 1819-LTP-SW-545-0201		Rev 0
<small>This drawing is not to be used in whole or part other than for the intended purpose and project as defined on this drawing. Refer to the contract for full terms and conditions.</small>									



0	30/06/2020	First issue.	PB			Project Highsted Road new footway, Sittingbourne.	Drawing status FOR CONSTRUCTION		
Rev	Revision Date	Purpose of revision	Drawn	Check'd	App'd		Scale	1:150 at A3	Do not scale
 <p>Kent County Council Ashford Highway Depot Henwood Industrial Estate Ashford TN24 8AD Tel: 03000 418181</p>						Drawing title Drainage and service ducts.	Drawing number 1819-LTP-SW-545-0501		Rev 0
						This drawing is not to be used in whole or part other than for the intended purpose and project as defined on this drawing. Refer to the contract for full terms and conditions.			



0	30/06/2020	Initial issue.	PB			Project	Highsted Road new footway, Sittingbourne.		Drawing status	FOR CONSTRUCTION	
Rev	Revision Date	Purpose of revision	Drawn	Check'd	App'd	Drawing title	Kerbs, footways and paved areas: Sheet 1 of 2.		Scale	1:150 at A3	Do not scale
 <p>Kent County Council Ashford Highway Depot Henwood Industrial Estate Ashford TN24 8AD Tel: 03000 418181</p>						<p>Drawing number</p> <p>1819-LTP-SW-545-1101</p> <p>Rev</p> <p>0</p>					
<p>This drawing is not to be used in whole or part other than for the intended purpose and project as defined on this drawing. Refer to the contract for full terms and conditions.</p>											




CUT LINE B


HB2
2 metres.
EF

2 metres.
EF

Edgings installed with uniform longitudinal fall from west to east.

© Crown Copyright and database right 2020.
Ordnance Survey 100019238.

0	30/06/2020	First issue.	PB			Project	Drawing status	
Rev	Revision Date	Purpose of revision	Drawn	Check'd	App'd	Highsted Road new footway, Sittingbourne.	Scale	FOR CONSTRUCTION
							1:150 at A3	Do not scale
 Kent County Council Ashford Highway Depot Henwood Industrial Estate Ashford TN24 8AD Tel: 03000 418181						Drawing title	Drawing number	Rev
						Kerbs, footways and paved areas: Sheet 2 of 2.	1819-LTP-SW-545-1102	0
<small>This drawing is not to be used in whole or part other than for the intended purpose and project as defined on this drawing. Refer to the contract for full terms and conditions.</small>								



Installed on new WB post with sign light.

--	--

Existing column to remain.	

Installed on new post.

--	--

Existing column to remain.	

Bollard (EHEB508) to be removed without replacement.	

New post (to be removed with sign not more than three months after completion).

--	--	--

Bollard (EHEB510) to be removed without replacement.

	Plain faced bollard (EHEB509).


New WB post and sign light.


--	--

0	30/06/2020	Initial issue.	PB			Project	Highsted Road new footway, Sittingbourne.		Drawing status	FOR CONSTRUCTION	
Rev	Revision Date	Purpose of revision	Drawn	Check'd	App'd	Drawing title	Traffic signs.		Scale	1:750 at A3	Do not scale
<p>Kent County Council Ashford Highway Depot Henwood Industrial Estate Ashford TN24 8AD Tel: 03000 418181</p>									Drawing number	1819-LTP-SW-545-1201	
									Rev	0	
<small>This drawing is not to be used in whole or part other than for the intended purpose and project as defined on this drawing. Refer to the contract for full terms and conditions.</small>											



Carriageway markings				
TSRGD diagram number	Mark (mm)	Gap (mm)	Width (mm)	Comments
1003A	600	300	200	
1004	4000	2000	100	Five marks on each approach to junction.
1009A	600	300	100	



0	30/06/2020	Initial issue.	PB			Project	Drawing status	
Rev	Revision Date	Purpose of revision	Drawn	Check'd	App'd	Highsted Road new footway, Sittingbourne.	Scale	FOR CONSTRUCTION
							1:150 at A3	Do not scale
 Kent County Council Ashford Highway Depot Henwood Industrial Estate Ashford TN24 8AD Tel: 03000 418181						Drawing title	Drawing number	
						Road markings.	1819-LTP-SW-545-1202	
							Rev	0
<small>This drawing is not to be used in whole or part other than for the intended purpose and project as defined on this drawing. Refer to the contract for full terms and conditions.</small>								